STREET PLANTING

Latin Name	Common Name	Scheduled Size	Spacing	Mature Height	Mature Spread	Qty
STREET TREE						
Libocedrus plumosa	Kawaka	45L	0	Placed	2.0 - 3.5m	8
WALKWAY PLANTING						
Carex virgata	Swamp sedge; pukio	1/2L	2 Plants/sq m	0.9 - 1.5m	0.6 - 0.9m	67
Chionochloa flavicans	Dwarf toe toe	1/2L	2 Plants/sq m	0.75 - 0.9m	0.9 - 1.2m	54
Coprosma 'Poor Knights'	Coprosma poor knights; taupata	1/2L	2 Plants/sq m	0.45 - 0.6m	0.9 - 1.2m	67
Libertia grandiflora	New Zealand iris	1/2L	2 Plants/sq m	0.6 - 0.75m	0.6 - 0.9m	40
Dianella nigra	Turutu	1/2L	3 Plants/sq m	0.5m	0.5m	60
SWALE PLANTING						
Apodasmia similis	Oioi	1/2L	3 Plants/sq m	1m	1m	121
Carex secta	Sedge; makura	1/2L	3 Plants/sq m	1m	1m	121
Cyperus ustulatus	Giant umbrella sedge	1/2L	3 Plants/sq m	1m	1m	101
Ficinia nodosa	Knobby Club Rush	1/2L	5 Plants/sq m	1.5m	1m	101
TOTAL						**755**

RAINGARDEN PLANTING

Latin Name	Common Name	Scheduled Size	Rate/Spacing	Mature Height	Mature Spread	Qty
Apodasmia similis	Oioi	1/2L	3 Plants/sq m	1m	1m	165
Carex dissita	Tussock, sedge; purei	1/2L	4 Plants/sq m	0.8m	0.8m	331
Carex secta	Sedge; makura	1/2L	3 Plants/sq m	1m	1m	165
TOTAL						**661**

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

- Stage boundary
- Scope of street landscape works
- Scope of green link landscape works

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN
OVERALL LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00
SCALES: 1:2000
A3

DRAWING No: A2111813-LA-600
REV AB

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingarden (part of this application)
	National Grid Yard (to be removed)
	Street Light (with 2m radius)

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

HG
AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00
SCALES: 1:200
A3

DRAWING No: A2111813-LA-601
REV AB

NORTH

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Kawaka sp. tree
	Michelia 'Star Bright' - implemented as part of DG14 works
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingardens (part of application)
	Street Light (with 2m radius)

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00
SCALES: 1:200
A3

DRAWING No: A2111813-LA-602
REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Kawaka sp. tree
	Michelia 'Star Bright' - implemented as part of DG14 works
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingardens (part of application)
	Street Light (with 2m radius)

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

HG
AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00 | SCALES: 1:200 | A3

DRAWING No: A2111813-LA-603 | REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Kawaka sp. tree
	Michelia 'Star Bright' - implemented as part of DG14 works
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingardens (part of application)
	Street Light (with 2m radius)
	Previous stage street tree, relocated due to service clash

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00 | SCALES: 1:200 | A3

DRAWING No: A2111813-LA-604 | REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Kawaka sp. tree
	Michelia 'Star Bright' - implemented as part of DG14 works
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingardens (part of application)
	Street Light (with 2m radius)

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00 | SCALES: 1:200 | A3

DRAWING No: A2111813-LA-605 | REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Kawaka sp. tree
	Michelia 'Star Bright' - implemented as part of DG14 works
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingardens (part of application)
	Street Light (with 2m radius)

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00 | SCALES: 1:200 | A3

DRAWING No: A2111813-LA-606 | REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY	
	Kawaka sp. tree
	Michelia 'Star Bright' - implemented as part of DG14 works
	Walkway Planting
	Swale Planting
	Footpath
	Grass Berm
	Proposed vehicle crossing
	Raingardens (part of application)
	Street Light (with 2m radius)

NOTES:

1. All street trees to be canopy lifted at minimum 2m during the maintenance period.
2. Minimum 100mm thick grade 4 organic bark mulch will be applied to the street planting areas.
3. All street trees are placed in accordance with AT TDM:
   - mature dripline 2m from street lights
   - trunk 2m from sumps and service lines.
4. All street trees are placed 2m away from vehicle corssings.
5. All planting to be set back 600mm minimum from path edges.
6. Vehicle crossings are indicative only, subject to future comprehensive designs.
7. Street tree locations may vary in the future subject to future vehicle crossings as part of on lot development.
8. This set of drawing to be read in conjucntion with engineering drawings.

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:

HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:

STREET LANDSCAPE PLAN

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00 | SCALES: 1:200 | A3

DRAWING No: A2111813-LA-607 | REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx

Lot 508 PLANTING					
ID	**Latin Name**	**Common Name**	**Scheduled Size**	**Spacing**	**QTY**
SPECIMEN TREES					
PE	Pittosporum eugenioides	Tarata	45L	Placed	4
PL	Pseudopanax crassifolius	Lancewood	18L	Placed	5
GROUNDCOVERS（154m2）					
Coh	Coprosma 'Hawera'	Groundcover Coprosma	1/2L	2 Plants/sq m	134
Cpk	Coprosma 'Poor Knights'	Coprosma poor knights; taupata	1/2L	2 Plants/sq m	134
Cvg	Carex virgata	Swamp sedge; pukio	1/2L	2 Plants/sq m	134
Pbr	Phormium 'Black Rage'	Black Flax	1/2L	2 Plants/sq m	134

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND

ISO 9001 QUALITY ASSURED

THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

KEY

- Tarata
- Lancewood
- Groundcovers
- Lawn
- Concrete - 8% black oxide concrete
- Concrete - 4% black oxide concrete
- Portland Bench or similar
- 9no. 200x200mm Timber Bollard
- 2no. 200x200mm Removable Bollard

Note:
1. All plated area to be implemeted with 100mm Grade 4 bark mulch or similar
2. Plant layout to be in groups of 3's/5's and 7's.
3. Refer to civil engineering drawings for hard landscape details.

AUCKLAND OFFICE
LEVEL 4, 96 ST GEORGES BAY ROAD
PARNELL AUCKLAND 1052
T +64 9 917 5000
W www.harrisongrierson.com

REF	REVISIONS	BY	DATE
AB	AS BUILT	WZD	16/03/23

PROJECT:
HUGH GREEN LIMITED
DONEGAL STAGE 16
36 TIR CONAILL AVENUE, FLAT BUSH

TITLE:
STREET LANDSCAPE PLAN
GREENLINK LANDSCAPE CONCEPT

ORIGINATOR: WZD	DATE: 06/10/21	SIGNED:	PLOT BY: WZD
DRAWN: WZD	DATE: 16/03/2023	SIGNED:	PLOT DATE: 06/04/23
CHECKED: LAB	DATE: 16/03/2023	SIGNED:	SURVEY BY: -
APPROVED:	DATE:	SIGNED:	SURVEY DATE: -

ISSUE STATUS: AS BUILT

PROJECT No: A2111813.00
SCALES: 1:200
A3

DRAWING No: A2111813-LA-620
REV AB

\\harrisongrierson.com\hgdata\Newmarket\Shares\Jobs\1050\A2111813.00_a DG 16\Landscape\DG16_StreetLandscape_EPA_AsBuilt_v2023.vwx